

APPROVED SCHEDULE - B

No. BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Drilling of borewell and installation of motor, pump and other accessories in ward no. 8, kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				Hosahalli Jaganath Sanjay Reddy	
				In Figures	In Words
1	2	Carrying out geophysical survey Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting gvenner or schiberger's method, including reconnaissance survey of geological formation, geophysical investigation of existing ground water in the vicinity, its quality and acceptability of the users indicating the licating the location of site, recommended.depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtrs in consolidated formation for proper seating of casting pipe, depth of drilling required to cover full depth of acquifer proposed to be tapped, probate yield and other information required including transportation and accessories to work site, engaging technical personal and labour required etc.	Nos	1900.0	Rupees One Thousand Nine Hundred Only
2	100	Sinking borewell of 165mm dia clear using super fast Hydraulic rig of capacity 250 PSIG na above 900 CFM and abaove in all strats including over burden upto 20M. fixing of casing pipes collars and cap with necessary, cutting and threading including transportation of rig and supporting vehicles, crew charges and cost of consumables etclm complete including yield testing at the final depth with a minimum work in on compression for an hour (excluding cost of casing pipes collars cap etc.,) Upto 50.00m depth	Rmtr	300.0	Rupees Three Hundred Only
3	100	Above 50.00 to 100.00m depth	Rmtr	400.0	Rupees Four Hundred Only
4	100	Above 100.00 to 150.00m depth	Rmtr	425.0	Rupees Four Hundred Twenty Five Only
5	100	Above 150m to 200m depth	Rmtr	450.0	Rupees Four Hundred Fifty Only
6	100	Above 200m to 250 m depth	Rmtr	550.0	Rupees Five Hundred Fifty Only
7	50	Above 250m to 300 m depth	Rmtr	550.0	Rupees Five Hundred Fifty Only
8	80	Supplying of ISI Mark 175 mm nominal bore, Plain end steel casing pipe grade of steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 medium black ERW casing pipe of 5mm thick black electric resistance welded steel tube material and confirming to IS 1387 / 1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5 to 7 mtr both ends threaded confirming to IS 554/1985 one end fixed with a socket confirming to is 4270:2001 and the other end with screwed pipes. All pipes shall be reasonably free from defects. The tubes shall be reasonably straight should be with ISI marking weighing 25.10kg/mtr. (Inclusive of all taxes and durties). Prices includes collar-medium duty.	Rmtr	1325.0	Rupees One Thousand Three Hundred Twenty Five Only
9	20	Providing 175mm dia MS Collar	Nos	100.0	Rupees One Hundred Only
10	2	Providing 175mm dia Bore Cap CE (M)	Nos	100.0	Rupees One Hundred Only
11	20	Providing and fixing 250mm dia PVC 10kg/sqm	Mtr	2500.0	Rupees Two Thousand Five Hundred Only
12	500	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifcatiions.	Mtr	450.0	Rupees Four Hundred Fifty Only
13	2	Atalanta, Suguna, CRI KIRLOSKAR and other equipments pumps 10.00 HP/7.5KV(20 stage)	Nos	50000.0	Rupees Fifty Thousand Only

Signature of the contractor

08/03

Approved Qty.	Description	Unit	Approved Tender Rates of		
			Hosahalli Jaganath Sanjay Reddy		
			In Figures	In Words	
14	1120	Supply and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS 8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100 Volts as per IS-694 : 1990 & confirming to GTP of GROUP-A.	Mtr	115.0	Rupees One Hundred Fifteen Only
15	2	Providing and fixing in position 50mm nominal bore non-return valve vertical type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications	Nos	1450.0	Rupees One Thousand Four Hundred Fifty Only
16	2	Supplying and fixing 50mm GI Union	Nos	200.0	Rupees Two Hundred Only
17	4	Supplying and fixing 50mm GI Elbow	Nos	100.0	Rupees One Hundred Only
18	4	Supplying and fixing 50mm GI Nipple	Nos	80.0	Rupees Eighty Only
19	4	Supplying and fixing 50mm GI Collar	Nos	80.0	Rupees Eighty Only
20	40000	Fabricating supplying and mounting MS box made out 14SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete.	Sq cms	0.3	and Thirty Paise Only
21	2	Supplying and fixing angle iron frame work fabricated out of M>S angle iron.. And M.S flat .. With bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint.(Page no.49, SI.No.6.39.2)50x50x6mm Electrical SR.2014-15	Mtr	300.0	Rupees Three Hundred Only
22	2	Supplying of TPST with rewirable porcelain Channels in SM encloser. Made out of 14 SWG powder coated paint of approved colour. 32 Amps	Nos	1800.0	Rupees One Thousand Eight Hundred Only
23	2	Supplying and fixing polished wood board made of not less than 15mm thick plank on both bsides of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws.	Each	270.0	Rupees Two Hundred Seventy Only
24	2	Supplying and fixing LED Type panel board indicating lamp with required colour suitable for 220V AC 50 Hz 12/24 DC	Nos	400.0	Rupees Four Hundred Only
25	2	Supplying fully automatic star-Delta starter unit push button type with suitable wires, 2 contactores, one adjustable thermal timer mounted on a common base palte held in steel encloser for use on 400/440 volts 3 phase and wired after fixing to the wooden board for motor. Upto 12.5HP	Nos	6500.0	Rupees Six Thousand Five Hundred Only
26	2	Suppling and fixing single phase preventor using necessary wires over an existing panel board suitable for motor up to 20HP capacities.	Nos	700.0	Rupees Seven Hundred Only
27	40	Wiring for lighting /power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP-A.4 sqmm	Mtr	35.0	Rupees Thirty Five Only
28	8	Supplying, fixing and wiring heavy duty low voltage capacitors confirming to IS 2834 Phase, 400/440 volts grade, for power factor improvement of rotating machinery.	KVAR	400.0	Rupees Four Hundred Only
29	2	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 40-63Amps TPN	Each	1900.0	Rupees One Thousand Nine Hundred Only
30	2	Supplying and fixing wiring earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.5mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia	Nos	2700.0	Rupees Two Thousand Seven Hundred Only

Signature of the contractor

Executive Engineer

S.No.	Approved Qty.	Description	Unit	Approved Tender Rates of Hosahalli Jaganath Sanjay Reddy	
				In Figures	In Words
31	10	Supplying and fixing class A (medium duty)-GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 K.V. class 40mm	Mtr	300.0	Rupees Three Hundred Only
32	50	Supplying of 1.1 KV LTUG Cable having alluminium conductor PVC insulated extruded inner sheathed , galvanized, steel strip (except 2C X 10sq.mm wire armoured) confirming to IS-3975:1990(No. of Strip indicated in GTP) & extruded PVC outer sheathed armored cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A.4 core 16 sqmm	Mtr	100.0	Rupees One Hundred Only
33	50	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe/on wall/on poles as required. In existing trench/duct. 6 sqmm to 16sqmm	Mtr	5.0	Rupees Five Only
34	60	Digging of trenches of 0.6 x 0.50m wide refilling the trench to the required ground level and consolidating etc., compelte	Mtr	85.0	Rupees Eighty Five Only
35	2	Supplying and fixing LT cast iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumin insulating compound compelte with terminals, clamps, bolts nuts and washers etc., for 16 sqmm	Each	250.0	Rupees Two Hundred Fifty Only
36	12	Supplying and fixing of procelin fuse channel with cutouts on existing wooden/panel using necessary nuts, bolts and washers. 63Amps	Each	200.0	Rupees Two Hundred Only
37	66.83	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications.	Cum	250.0	Rupees Two Hundred Fifty Only
38	315	Supplying PVC ring tight pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite rolling and lowering into trenches laying true line and level and perfect linking at joints testing and commissioning including loading and unloading at both destination and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approval type with all labour with all lead and lift including encasing the pipe around to a depth of not less than 15 cms with soft gravel or selected earth available from the excavation etc., compelte and giving necessary hydraluic test to the required pressure as per IS (Contractor will make his own arrangement for procuring water for testing)	Rmtr	50.0	Rupees Fifty Only
39	66.83	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications allow 60% of rate considered under item.	Cum	60.0	Rupees Sixty Only
40	2	Providing and fixing 65mm dia Gun metal non return valve Wheel valve conforming to IS specification of approved make as per directions including all lead and lift etc., compelte 50mm	Each	1350.0	Rupees One Thousand Three Hundred Fifty Only
41	21.87	Providing and laying in position plain cement concrete of mix M 20 with OPC cement @300 kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.43 cum with superplastisiser @ 3 lts confirming to IS 9103 - 1999 Reaffirmed - 2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation plinth and cills, including cost of all materials, labour HOM of machinery curing complete as per specifications.	Cum	5750.0	Rupees Five Thousand Seven Hundred Fifty Only
42	24	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete (internal work exposed on wall) 20mm nominal OD pipes	Rmtr	125.0	Rupees One Hundred Twenty Five Only
43	20	Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Each	215.0	Rupees Two Hundred Fifteen Only

Signature of the contractor

slu
08/03

Approved Qty.	Description	Unit	Approved Tender Rates of	
			Hosahalli Jaganath Sanjay Reddy	
			In Figures	In Words
44 38	Lead for disposal of debries shall be payable at carriage rates by mechanical means including loading and unloading as per 13.30 kms	Cum	100.0	Rupees One Hundred Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

08/03